


GENERAL NOTES

1. THE GENERAL CONTRACTOR SHALL CHECK AND VERIFY ALL DIMENSIONS AND CONTRADICTIONS AT PROJECT SITE BEFORE EXECUTING ANY WORK. HE SHALL NOTIFY THE OWNER AND/OR THE AUTHORIZED AGENT OF THE OWNER OF ANY AND ALL DISCREPANCIES BEFORE PROCEEDING. 2. WORKING DRAWINGS ARE NOT TO BE SCALED. DIMENSIONS SHALL GOVERN. DIMENSIONS ARE TAKEN AT FACE OF STUD OR CENTERLINE UNLESS NOTED OTHERWISE. ALL MATERIALS AND WORKMANSHIP SHALL BE NEW AND THE BEST OF ITS CLASS AND KIND. ALL CONTRACTORS SHALL COOPERATE WITH AND ANTICIPATE THE NEEDS OF EACH OTHER IN THEIR RESPECTIVE TRADES SO THAT THE WORK OF ONE WILL NOT UNNECESSARILY DELAY OR REQUIRE MODIFICATION TO THE WORK OF ANOTHER. ALL FEATURES OF CONSTRUCTION NOT SPECIFICALLY SHOWN SHALL BE OF THE SAME TYPE AND CHARACTER SHOWN FOR SIMILAR CONSTRUCTION. 3. EACH CONTRACTOR SHALL OBTAIN AND PAY FOR ALL PERMITS REQUIRED BY LEGAL AUTHORITIES BEFORE PROCEEDING WITH THEIR PROSPECTIVE INSTALLATION. HE SHALL ALSO ARRANGE AND PAY FOR ALL INSPECTIONS AND EXAMINATIONS REQUIRED BY THOSE AUTHORITIES. (UNLESS AGREEMENT WITH OWNER STATES OTHERWISE). 4. ALL WORK AND MATERIALS ARE TO COMPLY IN EVERY RESPECT WITH THE LATEST REQUIREMENTS OF ALL APPLICABLE CITY, COUNTY AND STATE CODES, LOCAL REGULATIONS AND THE DIRECTION OF THE BUILDING INSPECTOR FOR SUCH BUILDING LAWS. REGULATIONS AND DIRECTIONS ARE TO BE CONSIDERED AS PART OF THEIR SPECIFICATIONS AND PLAN, EXCEPT WHERE EXCEEDED HEREIN. 5. STRUCTURE IS DESIGNED AS STABLE PROVIDED ALL SHORING AND BRACING NECESSARY TO INSURE THE STABILITY OF ALL PARTS OF THE BUILDING DURING CONSTRUCTION. 6. WHERE FACTORY FINISHED OR FACTORY PRIMED ITEMS OCCUR SUCH AS GRILLES, DIFFUSERS, METAL TRIMS, AND ACCESSORIES, ETC., THEY SHALL DIRECTED BY BE PAINTED OR FINISHED TO MATCH THE ADJACENT SURFACE OR AS THE ARCHITECT. 7. PROVIDE SUPPORTS AS REQUIRED FOR DUCTS, PIPING, AND MECHANICAL AND ELECTRICAL INSTALLATIONS. PROVIDE APPROVED SWAY BRACING FOR WATER HEATER AND ALL SUSPENDED EQUIPMENT. 1. GENERAL CONDITIONS 1.1 ALL WORK SHALL COMPLY WITH APPLICABLE BUILDING CODES, INCLUDING: 1998 BUILDING STANDARDS ADMINISTRATIVE CODE, PART 1, TITLE 24, CCR 1998 CALIFORNIA BUILDING CODE (CBC), PART 2, TITLE 24, CCR 1997 UNIFORM BUILDING CODE, VOLUMES 1-3, w/ 1998 CALIFORNIA AMENDMENTS) 1998 CALIFORNIA ELECTRICAL CODE (CEC), PART 3, TITLE 24, CCR 1996 UNIFORM ELECTRICAL CODE WITH 1998 CALIFORNIA AMENDMENTS) 1998 CALIFORNIA MECHANICAL CODE (CMC), PART 4, TITLE 24, CCR 1996 UNIFORM MECHANICAL CODE WITH 1998 CALIFORNIA AMENDMENTS) 1998 CALIFORNIA PLUMBING CODE (CPC), PART 5, TITLE 24, CCR 1996 UNIFORM PLUMBING CODE WITH 1997 CALIFORNIA AMENDMENTS) 1998 CALIFORNIA FIRE CODE (CFC), PART 9, TITLE 24, CCR 1997 UNIFORM FIRE CODE WITH 1998 CALIFORNIA AMENDMENTS) 1998 CALIFORNIA REFERENCE STANDARDS CODE, PART 12, TITLE 24, CCR 1990 TITLE 19, CCR PUBLIC SAFETY, STATE FIRE MARSHALL REGULATIONS (SFRD CALIFORNIA FIRE MARSHALL CODE (C-F-M-C) WITH AMENDMENTS 1.2 THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK USING HIS BEST SKILL AND ATTENTION. THE CONTRACTOR SHALL ENFORCE STRICT DISCIPLINE AND GOOD ORDER AMONG HIS EMPLOYEES AND OTHER PERSONS CARRYING OUT THE CONTRACT. HE SHALL NOT PERMIT EMPLOYMENT OF UNFIT PERSONS OR PERSONS NOT SKILLED IN TASKS ASSIGNED TO THEM. THE CONTRACTOR SHALL BE RESPONSIBLE TO THE OWNER FOR THE ACTS OR OMISSIONS OR THE CONTRACTOR'S EMPLOYEES, SUBCONTRACTORS AND OTHER PERSONS PERFORMING PORTIONS OF THE WORK UNDER CONTACT WITH THE CONTRACTOR. 1.3 THE CONTRACTOR SHALL PROVIDE AND PAY FOR LABOR, MATERIALS, EQUIPMENT, TOOLS, CONSTRUCTION EQUIPMENT AND MACHINERY, WATER, UTILITIES, TOILETS, TRANSPORTATION AND OTHER FACILITIES AND SERVICES NECESSARY FOR THE PROPER EXECUTION AND COMPLETION OF THE WORK, WHETHER TEMPORARY OR PERMANENT AND WHETHER OR NOT INCORPORATED OR TO BE INCORPORATED INTO THE WORK. 1.4 CONTRACTOR SHALL ANTICIPATE ALL REQUIREMENTS FOR THE COMPLETION OF THE JOB AND PROVIDE ALL NECESSARY WORK SUCH AS CUTTING, PATCHING, REMOVALS, RELOCATIONS, FIXING, REPAIRING, PAINTING, ETC., WHETHER OR NOT SPECIFICALLY CALLED FOR OR DESCRIBED ON THE DRAWING. 1.5 CONTRACTOR SHALL VERIFY THE SITE AND EXAMINE ALL EXISTING CONDITIONS WHICH MAY AFFECT THE WORK AND REPORT TO ARCHITECT ANY DISCREPANCY WITH THE DRAWINGS OR THE NEED FOR ANY CLARIFICATIONS BEFORE SUBMITTING HIS BID. 1.6 ALL INFORMATION SHOWN ON THE DRAWINGS RELATIVE TO EXISTING CONDITIONS IS GIVEN AS THE BEST PRESENT KNOWLEDGE, BUT WITHOUT GUARANTEE OR ACCURACY. WHERE ACTUAL CONDITIONS CONFLICT WITH THE DRAWINGS, THEY SHALL BE REPORTED TO THE ARCHITECT SO THAT THE PROPER REVISIONS MAY BE MADE. MODIFICATIONS OR DETAILS OF CONSTRUCTION SHALL NOT BE MADE WITHOUT THE PRIOR WRITTEN APPROVAL OF THE ARCHITECT. 1.7 CONTRACTOR TO VERIFY WITH OWNER AND ARCHITECT MAKE, MODEL, AND COLOR OF APPLIANCES, ELECTRICAL AND PLUMBING FIXTURES, AND FINISH MATERIAL. CONTRACTOR SHALL COORDINATE WITH THE OWNER THE EXACT LOCATION OF ALL POWER, DATA, COMMUNICATION, AND TELEVISION RECEPTACLES AND SWITCHES. 1.8 THE CONTRACTOR AND HIS SUBCONTRACTORS MUST MAINTAIN THE PREMISES AND SURROUNDING AREAS CLEAN AT ALL TIMES AND MUST CLEAN THESE AREAS DAILY AT THE END OF WORKING HOURS. THE CONTRACTOR SHALL REMOVE FROM AND ABOUT THE PROJECT WASTE MATERIALS, RUBBISH, THE CONTRACTORS' TOOLS, CONSTRUCTION EQUIPMENT, MACHINERY, AND SURPLUS MATERIALS. THE CONTRACTOR SHALL CLEAN ALL GLASS, CERAMIC TILE, FINISH HARDWARE, PLUMBING FIXTURES, ELECTRICAL TRIM, EQUIPMENT, AND APPLIANCES AND THE BUILDING UPON COMPLETION OF THE PROJECT. 1.9 THE PLUMBING, MECHANICAL, AND ELECTRICAL CONTRACTORS SHALL SUPPLY LAYOUTS, CALCULATIONS, SIZES, SPECIFICATIONS AND NECESSARY PERMITS FOR THEIR RESPECTIVE WORK AND SHALL PROVIDE COPIES OF SAME TO THE ARCHITECT. 1.10 ALL WORK AND MATERIAL SHALL COMPLY WITH THE CURRENT EDITION OF ALL PERTINENT UNIFORM BUILDINGS CODES AND AGENCIES' REGULATIONS, LAWS AND ORDINANCES GOVERNING THIS CONSTRUCTION. NOTHING IN THE CONSTRUCTION DOCUMENTS SHALL BE CONSTRUED TO PERMIT AN INSTALLATION IN VIOLATION OF APPLICABLE CODES AND/OR RESTRICTIONS. THE CONTRACTOR SHALL NOTIFY THE ARCHITECT IF THE DOCUMENTS VARY FROM SAID CODES AND/OR RESTRICTIONS.	1.11 DELIVERY OF MATERIALS AND REMOVAL OF DEBRIS IS TO BE COORDINATED AND SCHEDULED WITH THE OWNER AND CITY AGENCIES IF REQUIRED. MATERIAL AND EQUIPMENT STORAGE AND THE SECURITY OF SAME INCLUDING THE JOB SITE ARE THE RESPONSIBILITY OF THE CONTRACTOR. 1.12 THE ACT OF STARTING ANY SPECIFIC OPERATION WILL BE DEEMED AS EVIDENCING ACCEPTANCE BY THE CONTRACTOR OF ALL RELATED EXISTING CONDITIONS AS BEING SATISFACTORY FOR SUCH WORK. 1.13 CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS, AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD THE OWNER AND ARCHITECT HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OR WORK ON THIS PROJECT. OBSERVATION VISITS TO THE SITE BY FIELD REPRESENTATIVES OF THE ARCHITECT SHALL NOT INCLUDE INSPECTIONS OF PROTECTIVE MEASURES OR CONSTRUCTION PROCEDURES. THESE VISITS ARE PERFORMED SOLELY FOR THE PURPOSE OF ASSISTING IN QUALITY CONTROL AND ACHIEVEMENT OF GENERAL CONTRACTOR'S PERFORMANCE AND SHALL NOT BE CONSTRUED AS CONTINUOUS AND DETAILED INSPECTION OR SUPERVISION OF CONSTRUCTION. 1.14 APPROVED TOILET FACILITIES SHALL BE PROVIDED AT ALL TIMES DURING CONSTRUCTION. CHEMICAL TOILETS WHEN USED, SHALL NOT BE PLACED WITHIN THE FRONT YARD SETBACK. 1.15 THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES ON ADJACENT TO OR SERVING THE SITE BEFORE COMMENCING WORK. THE CONTRACTOR IS TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTORS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES ON, ADJACENT TO OR SERVING SITE. 1.16 VERIFY THE LOCATIONS AND SIZES OF METER BOXES AND MECHANICAL ROOM REQUIREMENTS WITH THE UTILITY PLANS AND THE WATER AND POWER DEPARTMENT. 1.17 ALLOW FOR COORDINATION AND MODIFICATION OF ADDITIONAL WORK FOR INSTALLATION OF FEEDER CONDUITS AND GAS LINES FROM MAIN SERVICES TO EACH DWELLING UNIT AND HOUSE PANELS(S). FOUNDATION CONCRETE SEE STRUCTURAL "S" SHEETS FOR NOTES. REINFORCING STEEL SEE STRUCTURAL "S" SHEETS FOR NOTES. STRUCTURAL STEEL SEE STRUCTURAL "S" SHEETS FOR NOTES. MASONRY SEE STRUCTURAL "S" SHEETS FOR NOTES. LUMBER/FRAMING SEE STRUCTURAL "S" SHEETS FOR NOTES. 6. FINISH CARPENTRY 6.1 FURNISH AND INSTALL ALL TRIM, DOORS FRAMES, PANELING, SHELIVING, ETC. INSTALL ALL FINISH HARDWARE, BATH ACCESSORIES, CABINET PULLS. ETC 6.2 ALL JOINTS TO BE TIGHT, TRUE, AND SECURELY FASTENED, CORNERS NEATLY BUTTED, COPED OR MITERED, WITH NAILS SET AND FREE OF TOOL MARKS. 6.3 WOOD WORK TO BE SCRIBED TO ADJOINING SURFACES, AND COMPLETELY SANDED AND PREPARED FOR FINISH. 6.4 ALL MATERIAL SHALL BE FULL LENGTH BOARDS WHEREVER POSSIBLE. 6.5 DOOR FRAMES SHALL BE SET PLUMB AND TRUE, RIGIDLY SECURED AND PROTECTED DURING THE COURSE OF CONSTRUCTION. 6.6 DOORS SHALL BE ACCURATELY CUT, TRIMMED AND FITTED TO FRAME AND HARDWARE WITH DUE ALLOWANCES FOR PAINTER'S FINISHES AND FLOORING. DOORS SHALL OPERATE FREELY BUT NOT LOOSELY OR HINGE BOUND WITH ALL HARDWARE PROPERLY ADJUSTED AND FUNCTIONING. 6. WOOD CASEWORK 6.7 ALL CABINETS AND CASEWORK TO CONFORM WITH WIC, MANUAL OF MILLWORK. USE CUSTOM GRADE WITH ROLLER GUIDE DRAWERS AND HIDDEN DOOR HINGES. CABINETS TO BE STAIN GRADE. 7. THERMAL AND MOISTURE PROTECTION 7.1 SHEET METAL a. GALVANIZED SHEET METAL PER ASTM A93 IN GAUGES NOTED ON DRAWINGS b. NAILS SHALL BE HOT DIPPED GALVANIZED. c. RIVETS SHALL BE RUST RESISTANT COATED SOFT IRON. d. SOLDER PER ASTM B32, 50% LEAD, 50% TIN. e. WHERE INDICATED ON DRAWINGS, PROVIDE COPPER FLASHING IN THICKNESS PER DETAILS. COPPER METAL CANNOT COME IN CONTACT WITH OTHER METALS, PROVIDE COPPER FASTENERS, ETC. FOR COPPER FLASHING INSTALLATION. ALL EXPOSED COPPER FLASHING TO BE CHEMICALLY TREATED TO PATINA WITHOUT DRIPS OR RUNS. CONTRACTOR TO PROVIDE SAMPLE FOR OWNER AND ARCHITECT APPROVAL PRIOR TO INSTALLATION. f. FABRICATE AND INSTALL ALL WORK IN ACCORDANCE WITH SHEET METAL AND AIR CONDITIONING CONTRACTOR'S ASSOCIATION ARCHITECTURAL SHEET METAL MANUAL. g. ALL DIMENSIONS SHALL BE FIELD VERIFIED. h. PROVIDE NECESSARY EXPANSION AND CONTRACTION JOINTS. i. EXPOSED RAW EDGES SHALL BE DOUBLED BACK 1/4" MINIMUM. 7.2 SEALANTS a. JOINTS SHALL BE CAULKED WITH ONE-PART, NON-SLAG, LOW MODULUS, MOISTURE CURING POLYURETHANE JOINT SEALANT, INSTALLED IN STRICT ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. APPLY SEALANT AS REQUIRED TO PROVIDE A POSITIVE BARRIER AGAINST MOISTURE AND AIR INFILTRATION. SEALANT COLOR TO MATCH ADJACENT SURFACE COLOR. b. EXTRUDED NEOPRENE PER ASTM D750. c. FILL ALL JOINTS WITH APPROVED FLEXIBLE OPEN-CELL POLYETHYLENE FOAM ROD BACKUP MATERIAL TO PROVIDE A BOND BREAK AT BACK OF JOINT.	7.3 WALLS a. ALL EXTERIOR WALLS TO HAVE A MINIMUM 15LB FELT UNDERLAY. PROVIDE TWO LAYERS OF GRADE 'D' PAPER UNDER EXTERIOR PLASTER APPLIED OVER WOOD SHEATHING PER U.B.C. c. CORROSION RESISTANT WEEP SCREED WHICH WILL ALLOW TRAPPED WATER TO DRAIN TO THE EXTERIOR OF THE BUILDING IS REQUIRED BELOW THE STUCCO AT THE FOUNDATION PLATE LINE. d. FLASH ALL EXTERIOR OPENINGS WITH APPROVED WATERPROOF KRAFT PAPER TO AT LEAST 6" UNDER THE BUILDING PAPER BEHIND THE WALL COVERING. FLASH ALL WINDOW AND DOOR FRAME HEADS WITH GALVANIZED METAL PER SHEET METAL NOTE 1. 7.4 INSULATION a. ALL INSULATION SHALL COMPLY WITH ENERGY INSULATION STANDARDS ADOPTED IN THE 1998 MODEL ENERGY CODE IN THE APPENDIX OF THE 1998 U.B.C.. FACING MATERIALS SHALL HAVE MAXIMUM RATINGS OF 25 FOR FLAME SPREAD AND 450 FOR SMOKE DENSITY. SEE TITLE 24 REQUIREMENTS SECTIONS FOR ADDITIONAL INFORMATION. b. ALL WALLS TO HAVE R-19 BATT TYPE INSULATION UNLESS NOTED OTHERWISE ON PLANS, AND ALL CEILINGS TO HAVE R-30 BATT TYPE INSULATION. c. INSTALL BATTS BETWEEN JOISTS SECURELY FITTED AT ALL CEILING AREAS EXPOSED TO ROOF OR ATTIC AREAS AND BETWEEN STUDS AT ANY VERTICAL WALL AREAS EXPOSED TO THE EXTERIOR, TO ATTIC SPACES OR TO UNCONDITIONED SPACES. 7.5 WATERPROOFING a. MEMBRANE WATERPROOFING WHERE INDICATED ON PLANS. PROVIDE "BITUTHENE 3000 WATERPROOFING MEMBRANE" BY GRACE CONSTRUCTION PRODUCTS. INSTALLATION TO BE PREPARED SURFACES BY SKILLED AND QUALIFIED MECHANICS PER STRICT ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS. 7. ROOFING 7.6 TILE ROOFING a. PATCH & REPAIR ROOF TO MATCH EXISTING AS REQUIRED. b. INSTALLATION SHALL BE AS PER MANUFACTURER'S SPECIFICATIONS. c. VERIFY COLOR AND PATTERN WITH OWNER AND ARCHITECT. 8. GLASS AND GLAZING 8.1 ALL GLASS USED FOR GLAZING EXTERIOR OPENING SHALL BE LIMITED IN AREA AND IN THICKNESS AS PER SECTIONS 2403& 2404. 8.2 ALL GLASS LESS THAN 18" ABOVE ADJACENT WALKING SURFACE SHALL BE FULLY TEMPERED PER ANSI STANDARD 297.1. 8.3 ALL SLIDING GLASS DOORS AND GLAZING IN DOORS SHALL BE TEMPERED GLASS 9. GYPSUM WALLBOARD 9.1 GYPSUM WALLBOARD SHALL BE "HARDROCK" 5/8" FIRE X CONFORMING TO ASTM C-36-92. 9.2 INSTALLATION SHALL BE PER MANUFACTURER'S SPECIFICATIONS WITH SCREW TYPE ATTACHMENT TO WOOD FRAMING. 9.3 CORNER REINFORCEMENT SHALL BE GALVANIZED STEEL TYPE, 90 DEGREE EDGES, UNLESS NOTED OTHERWISE. 9. FLOORING 9.7 CERAMIC TILE: TILE TO BE INSTALLED IN STRICT ACCORDANCE WITH CERAMIC TILE INSTITUTE STANDARDS. VERIFY MANUFACTURER, SIZE, SHAPE, COLOR AND PATTERN WITH OWNER AND ARCHITECT. 9.8 STONE TILE FLOORING: TILE FLOORING SHALL BE INSTALLED IN STRICT ACCORDANCE WITH CERAMIC TILE INSTITUTE STANDARDS TO PREPARED AND COMPLETELY CURED CONCRETE FLOOR. VERIFY SIZE, SHAPE, SPECIES AND PATTERN WITH OWNER AND ARCHITECT. 9. PAINTING 9.9 PROVIDE AND INSTALL "DUNN-EDWARDS" PAINT AND STAIN IN FINISHES AND COLORS AS DIRECTED BY THE OWNER AND ARCHITECT IN STRICT ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS BY SKILLED MECHANICS TO COMPLETELY PREPARED SURFACES. HANDLE PAINT PRODUCTS IN A MANNER CONSISTENT WITH LOCAL AND STATE CODES AND ENVIRONMENTAL REGULATIONS. 15. MECHANICAL 15.1 INSTALL COMPLETE PLUMBING SYSTEM IN ACCORDANCE WITH THE LATEST EDITION OF THE UPC AND LOCAL CODES. SYSTEM TO INCLUDE HOT AND COLD WATER, WATER HEATER AND RECIRCULATION PUMP, SOIL AND VENT PIPING, GAS PIPING, ETC. 15.2 ALL STEAM AND CONDENSATE RETURN PIPING AND ALL CONTINUOUSLY CIRCULATION DOMESTIC HOT WATER PIPING SHALL BE INSTALLED AS REQUIRED BY THE LATEST EDITION OF THE PLUMBING CODE. 15.3 PLUMBING CONTRACTOR TO COORDINATE WITH THE STRUCTURAL ENGINEER & FRAMING CONTRACTOR TO MINIMIZE MODIFICATION OF THE FRAMING, ESPECIALLY TOP PLATES, SHEAR WALLS AND STRUCTURAL MEMBERS. DRILL SMALLEST HOLE POSSIBLE THROUGH FRAMING. 15.4 WATER CLOSETS SHALL BE 1.6 GALLONS PER FLUSH PER HEALTH AND SAFETY CODE SECTION 17921.3B. 15.5 F.A.U. OR A.H.U. COMPARTMENTS DIMENSIONS SHALL INCLUDE A 3" MINIMUM CLEARANCE ON SIDES AND BACK, 6" MINIMUM CLEARANCE FROM FRONT OF EQUIPMENT FOR COMBUSTION AIR INTAKE. 15.6 PROVIDE COMBUSTION AIR OPENING AREA OF 1 SQ. IN. PER 1000 BTU (100 SQ. IN. MINIMUM) 2 SQ. IN. PER 1000 BTU (200 SQ. IN. MINIMUM) IS REQUIRED INTO COMPARTMENT, WITH ONE-HALF OF THE AREA WITHIN 12" OF THE CEILING AND ONE-HALF THE AREA WITHIN 12" OF THE FLOOR. 15.7 COMBUSTION AIR FROM ATTIC SPACE THROUGH 26 GAUGE GALVANIZED STEEL SLEEVE, UNSCREENED, EXTENDING A MINIMUM OF 6" ABOVE CEILING JOISTS. THE ATTIC SHALL BE PROVIDED WITH ADEQUATE VENTILATION. 15.8 COMBUSTION AIR FROM OUTSIDE AIR TO COMPARTMENT SHALL BE PROVIDED WITH 1/4" SCREEN AT THE OUTSIDE OPENING. 15.9 SEPARATE DUCTS SHALL BE PROVIDED FOR UPPER AND LOWER COMBUSTION AIR SUPPLY OPENINGS. 15.10 PROVIDE A CONSPICUOUSLY MARKED EXTERIOR GAS SHUT OFF VALVE. 15.11 PROVIDE A SEISMIC GAS SHUTOFF VALVE INSTALLED ON EACH FUEL GAS LINE FOR NEW BUILDINGS. 16. ELECTRICAL 16.1 ALL WORK SHALL BE IN FULL CONFORMANCE WITH ALL CODES, RULES AND REGULATIONS OF GOVERNING AGENCIES HAVING JURISDICTION OVER THE PROJECT AND SHALL COMPLY WITH THE REQUIREMENTS OF THE SERVICE POWER AND COMMUNICATION COMPANIES. 16.2 ALL EQUIPMENT, SWITCHES AND OUTLETS INSTALLED OUTDOORS AND EXPOSED TO WEATHER SHALL BE WATERPROOF AND HAVE GROUND FAULT PROTECTION. 16.3 RECEPTACLES SHALL BE INSTALLED VERTICALLY AT 12" A.F.F. U.N.O. 16.4 ALL ELECTRICALLY OPERATED FIXTURES, OUTLETS, EQUIPMENT OR DEVICES WHETHER INSTALLED BY THE ELECTRICAL CONTRACTOR OR OTHERS SHALL BE FULLY CONNECTED. 16.5 ALL OUTLETS AT EXTERIOR, GRADE LEVEL ACCESS, IN BATHROOMS, IN GARAGES AND COUNTER TOPS WITHIN 6'-0" OF SINKS SHALL BE GROUND FAULT PROTECTED. 16.1 SMOKE DETECTORS 16.1.1 SMOKE DETECTORS SHALL BE INSTALLED IN COMPLIANCE WITH APPLICABLE CODES. 16.1.2 SMOKE DETECTORS SHALL RECEIVE THEIR PRIMARY POWER FROM THE BUILDING WIRING AND SHALL BE EQUIPPED WITH A BATTERY BACK-UP. 20 MISCELLANEOUS 20.1 PROVIDE 5/8" TYPE "X" GYPSUM BOARD AT WALLS AND CEILING OF ENCLOSED USABLE SPACE UNDER STAIRS. 20.2 PROVIDE CLEARANCE FROM COMBUSTIBLES PER SECTION 3102.7.8, UBC 20.3 THRESHOLDS TO BE A MAXIMUM OF 1/2" ABOVE ADJACENT FLOOR. ALL EXTERIOR SWINGING DOORS TO OPEN OVER A LANDING 44" MINIMUM IN LENGTH BY A WIDTH OF 4" WIDER THAN EXIT DOOR. MINIMUM EXIT DOOR WIDTH 32"															
Onuma & Associates <i>Architecture, Planning, Consulting</i> 511 Mission Street South Pasadena, CA 91030 tel 626. 799. 9920 fax 626. 799. 8260 e-mail: info@onuma.com Consultants																	
RENOVATION PROJECT FOR SAINT EDMUND'S EPISCOPAL CHURCH 1175 SAN GABRIEL BLVD., SAN MARINO, CA., 91108-8048 STAMPS  REVISIONS <table><thead><tr><th>DESCRIPTION</th><th>DATE</th><th>BY</th></tr></thead><tbody><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr></tbody></table> PROJECT NUMBER 2000 SCALE AS NOTED PRINTED 08/24/2000 TITLE GENERAL NOTES SHEET T1 2 OF 44			DESCRIPTION	DATE	BY												
DESCRIPTION	DATE	BY															